



- LEGEND**
- EXISTING WETLAND AREAS
 - PERMANENTLY IMPACTED WETLAND AREA (DISTURBED AREA)
 - TEMPORARILY IMPACTED WETLAND AREA (DISTURBED AREA)
 - WETLAND MITIGATION AREA

TOTAL PERMANENTLY DISTURBED WETLAND AREA (MITIGATION AREA) = 292 SQ. FT.

TOTAL TEMPORARILY DISTURBED WETLAND AREA (RESTORATION AREA) = 434 SQ. FT.

WETLAND MITIGATION AREA (2:1) = 585 SQ. FT.

- NOTES:**
1. PRIOR TO CONSTRUCTION, WILL PLACE TEMPORARY FENCE (PLASTIC) AT LOCATIONS SHOWN ON THIS SHEET.
 2. WETLAND TOPSOIL EXCAVATED FROM THE DISTURBED AREAS SHALL BE USED AT THIS SITE. WETLAND TOPSOIL SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES AND STOCKPILED PRIOR TO GRADING AND STORM DRAIN CONSTRUCTION. SOIL FROM THESE AREAS SHALL BE PLACED IN THE RESTORATION AND MITIGATION AREAS. STORAGE AND STOCKPILED OF THESE SOILS WILL BE ALLOWED FOR A MAXIMUM OF 8 DAYS AND KEPT MOIST USING WATER FROM AN APPROVED SOURCE. IT IS ESTIMATED THAT 28 CU. YDS. WILL BE EXCAVATED AND PLACED.
 3. PLACEMENT OF WETLAND SOILS SHALL OCCUR AFTER THE RESTORATION AND MITIGATION AREAS HAVE BEEN PREPARED FOR WETLAND TOPSOIL AT THE DIRECTION OF THE ENGINEER.
 4. ONCE THE WETLAND TOPSOIL HAS BEEN PLACED, NO EQUIPMENT WILL BE ALLOWED TO OPERATE IN THE AREAS. TEMPORARY FENCE SHALL BE RESET TO PROTECT THE ENTIRE RESTORATION AREA.

Print Date: 10/6/2008		Sheet Revisions				As Constructed		EXHIBIT 'A'		Project No./Code	
Drawing File Name: wtpl4-Mile01.dgn		Date:	Comments			No Revisions:				STE C070-026	
Horiz. Scale: 1:60						Revised:		Designer: JAW	Structure	15393	
Unit Information						Void:		Detailer: JCM	Numbers		
								Sheet Subset: WETLAND	Subset Sheets: WT1 of 1	Sheet Number	